Date:

To Damak Municipality
Office of the Municipal Executive
Damak, Jhapa

Rate of Token System for Damak Hospital

SN	Item	Unit	Qty	Rate	Total
1	**Queue Management Software as a Service** Controls all QMS hardware units Real time view of queue status Web based statistical reporting Warning escalation to management	years	3		
2	Kiosk Wall Mount Wall mount kiosk 17" Infrared Touch Monitor High speed thermal printer with auto cutter Printing speed 150mm/sec Built in CPU	pcs	1		
3	Dispenser 4 Switch with Ethernet Interface 4 switches supporting 4 service categories Audio amplifier High speed thermal printer	set	2		
4	Dual Band Gigabit Ceiling Mount Access Point 802.11ac Wave2, 1267Mbps,2x2 @2.4 GHz, 2x2 @5 GHz, 2 x 10/100/1000 Base-T, Warranty 1 Year	pcs	3		
5	Counter Display Indoor (LED Matrix) 64 x 32 Full color Resolution: 64 x 32 pixels 2.4Ghz wireless 320 x 160 mm display size	pcs	16		
6	Client Software Allows user to get logged into QMS Server Acts as a graphical Interface for the teller. Displays the Counter number that is assigned to the respective counter. Has provisions to: Call next customer. Put the customer back into queue Transfer the assigned customer number to some other tellers Specialty call specific token out of queue Use user defined function keys instead of mouse clicks. Can be operated in mini mode or Normal mode.	pcs	6		
7	Keypad - Wifi Uses 4X4 matrix keypad 16 characters 2 line LCD with backlight Can be used in counters where computers are not available Communication Interface: Wifi Has provisions to: Call next customer. Put the customer back into queue Transfer the assigned customer number to some other tellers	pcs	20		

8	4 row multi diverter Display Indoor, Full Color 5 mm Resolution, 640mm width 480mm height (128pixels x 96 pixels), WiFi Communication. (must have feature of incrementing token number by certain fixed number department wise for efficient Queue Management)	pcs	3		
9	Speaker Unit (PS-300T) 10W Wall Mount, Speaker System consists of woofer & dome tweeter. 10W RMS / 15W Max, 8Ω, SPL at 1kHz (1W/1m): 86dB	pcs	4		
10	Thermal Paper	pcs	100		
12	Cables & Connectors Various cables like , Audio Cable, Power Cables Various Connectors like RJ45, Power Sockets etc..	ls	1		
13	Transportation Charge Delivery of equipment upto the site via Transport	ls	1		
14	Installation and Training Charges (Easy-Q) Installation of equipment Basic System Operation Training	ls	1		
Total					
13% VAT					
Total with VAT					
All the Equipments provided must have 3 years warranty against any manufacturing Defects					

Submitted By: