



"औद्योगिक, पर्यटकीय र हरित नगर, स्वच्छ, सुरक्षित र समृद्ध नगर"

दमक नगरपालिका नगर कार्यपालिकाको कार्यालय



फोन: ०२३-५८००४४, ५८०१३७, ५८०५०२
www.damakmun.gov.np
info@damakmun.gov.np

प.सं.: ०८२/८३/योजना
च.नं. ५६२६

मिति: २०८२/१२/३०

विषय: दरभाउपत्र पेश गर्नुहुन ।

श्री सूचीकृत फर्म/कम्पनीहरु,
सबै ।

चालु आ.व. ०८२/८३ को वार्षिक स्वीकृत कार्यक्रम अन्तर्गत दमक नगरपालिका, नगर कार्यपालिकाको कार्यालय परिसरभित्र नगर प्रहरी कन्ट्रोल रुम (Control Room) निर्माण कार्य गर्नुपर्ने भएको हुँदा यसै सूचना साथ संलग्न Bill of Quantities (BOQ) बमोजिमको कार्य के कति मा गर्न सकिन्छ? भन्ने विवरण खुलाई तपशिल बमोजिम हुने गरी प्रस्ताव पेश गर्नुहुन यस प्रकृतिका निर्माण कार्य गर्न इजाजत प्राप्त गरी सूचीकृत भएका सबै फर्म/कम्पनी हरुलाई अनुरोध गरिन्छ । सूचीकृत नभएका फर्म/कम्पनीहरुले सूचीकृत हुने प्रक्रिया पूरा गरी प्रस्ताव पेश गर्न सक्नुहुनेछ ।

- प्रस्ताव पेश गर्ने अन्तिम मिति: २०८३/०१/०७ गते कार्यालय समयभित्र ।
- पेश गर्ने विधि: कार्यालयमा उपस्थित भएर वा इमेल मार्फत info@damakmun.gov.np वा damakyojana@gmail.com मा ।
- दरभाउपत्र साथ संलग्न राख्नुपर्ने कागजातहरु:
 - यस नगरपालिकामा सूचीकृत भएको निस्सा प्रमाण
 - कम्पनी/फर्म दर्ता प्रमाणपत्रको प्रतिलिपी
 - भ्याट दर्ता प्रमाणपत्रको प्रतिलिपी
 - आ.व. ०८१/८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपी
 - अद्यावधिक भएको निर्माण इजाजतपत्रको प्रतिलिपी
- थप जानकारीका लागि यस कार्यालयको योजना तथा मूल्याङ्कन शाखामा कार्यालय समयभित्र सम्पर्क गर्न सक्नुहुनेछ ।

.....
२०८२/१२/३०

सुजिला निरौला
प्रमुख प्रशासकीय अधिकृत

Damak Municipality
Office of the Municipal Executive
BOQ

Project name: प्रही कन्टोन रुम निर्माण
Location: Damak, 1 Jhapa

सुनिल निरौला
प्रमुख प्रशासकीय अधिकृत

| SN. | Description of Works | Quantity | Unit | Rate | Amount | Remarks |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|------|--------|---------|
| 1.00 | Site, Clearance, works Befor & After construction Diversion, Dewatering, Rehabilitation & Dismantling old structures & disposal, Septic tank and | 1.00 | ls | | | |
| 2.00 | sand/gravel filling Ground with good quality Gravel sprinkling water, ramming & consolidating with all complete. | 3.59 | cum | | | |
| 3.00 | Plain cement concrete work (1:2:4) and foundation work with cement, sand & crushed aggregate of 10 mm to 38 mm gauge including mixing with mixture machine and compaction by vibrator, laying in line and level with curing all types of works as per specification and instruction of site engineer | 1.80 | cum | | | |
| 4.00 | Providing and laying brickwork in (1:4) super structure with approved quality first class chimney made brick in perfect line and level, finished including wetting the bricks, packing the joints and curing the work and necessary scaffolding, complete in all types and thickness of walls, columns, etc. as per drawings, specification | 3.19 | cum | | | |
| 5.00 | cement sand mortar plaster in (1:4) work on wall surface with proper curing all complete work | 42.11 | sqm | | | |
| 6.00 | Plain cement concrete M20 for R.C.C work with cement, sand & crushed aggregate of 10mm to 38 mm gauge including mixing with mixture machine & compaction by vibrator, laying in line and level with curing the job in all types of R.C.C works complete as per specification & instruction by the | 2.29 | cum | | | |
| 7.00 | Tor/TMT Reinforcement work for RCC work including supply, straighting, cutting, binding and laying of different diameter steel rod in all types of RCC work as per design, drawing, specification and | 159.41 | kg | | | |
| 8.00 | Centring & shuttering works with local Hardwood including plastic sheet & nails complete | 18.32 | sqm | | | |
| 9.00 | white washing paint Two coat of approved colour and shade as per specification and instruction all complete | 42.11 | sqm | | | |
| 10.00 | Supplying, Fitting, Fixing Aluminium Framed Casement Door one way openable with Anodized Colour in the Section of 88x45 x1.0 mm All complete works. | 1.95 | sqm | | | |

| | | | | | | |
|-------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----|-------------------|--|--|
| 11.00 | Aluminium Framed Fixed Partition with Anodized Colour in the Section of 88 x 45 x 1.5 mm including 5 mm thick Glass or Board 9mm Laminated with one | 11.00 | sqm | | | |
| 12.00 | Aluminium Framed Fixed Partition with Anodized Colour in the Section of 88 x 45 x 1.5 mm including 5 mm thick Glass or Board 9mm Laminated with one side openable Door.(only) | 15.00 | nos | | | |
| 13.00 | Supplying, Fitting, Fixing 6mm plywood with Support Wood All complete works. | 13.33 | sqm | | | |
| 14.00 | Electric Works | 1.00 | ls | | | |
| | | | | Sub-Total= | | |
| | | | | 13% vat | | |
| | | | | Total | | |
| | | | | | | |

मिक नगरपालिका
कार्यपालिकाको कार्यालय
दमक-१
कोशी प्रदेश, नेपाल
२०७३

9

सुनिल निरौला
प्रमुख प्रशासकीय अधिकारी