



"औद्योगिक, पर्यटकीय र हरित नगर, स्वच्छ, सुरक्षित र समृद्ध
नगर"

दमक नगरपालिका नगर कार्यपालिकाको कार्यालय



प.सं.: २०८२/८२३

च.नं.: २२६८

दमक, झापा,
कोशी प्रदेश, नेपाल

फोन नं: ०२३५९७०००



मिति:- २०८०।०८।२२

श्री सूचीकृत निर्माण व्यवसायी फर्म / कम्पनिहरु। २०७३

विषय:- दररेट पेश गर्ने सम्बन्धमा

प्रस्तुत विषयमा दमक नगरपालिकाको परिसर भित्र प्यानल बोर्ड, जेनेरेटको केबल, चेन्जओभर तथा अन्य बिद्युतिय सामाग्री जडान गर्नु पर्ने भएकोले इच्छुक निर्माण व्यवसायी फर्म / कम्पनिहरुले यसैसाथ संलग्न दररेट (BOQ) भरि मिति २०८२।०८।२६ गते दिनको १:३० भित्र निवेदन सहित पेश गर्नहुन जानकारीको लागि यो सूचना प्रकाशित गरिएको छ

पेश गर्नु पर्ने आवश्यक कागजातहरु

- १) फर्म कम्पनि दर्ताको प्रतिलिपि
- २) अघिल्लो आ. ब.कर चुक्ताको प्रतिलिपि
- ३) भ्याट दर्ता प्रमाणपत्रको प्रतिलिपि

२०८०।०८।२२
सुनिल निरौला
प्रमुख प्रशासकीय अधिकृत



Damak Municipality
Office of Municipal Executive
Damak, Jhapa
Koshi Province, Nepal




Bill of Quantity(B.O.Q)

योजना :- कार्यालयमा जेनेरेटर ,बिद्युतिय प्यानल बोर्ड तथा चेन्ज ओभर जडान ।

Date:-2082/08/22

स्थान :- दमक नगपालिका कार्यालय ।

S.N.	Particular	Unit	Quantity	Rate	Amount	Remarks
1	Supply delivery Installation of 95sq.mm 4 core Armored copper power Cable N/S (NEA Merer to change over switch, chang over switch to panel board & Generator) .	Meter	45			
2	Supply delivery embedding & installatioon of (600*600*3mm) electrolytically pure copper plateat lesst 3m below the ground level surrounded by alternat layer of charcoal & common salt to thick-ness of 300mm around the electrode effectively grounded by means of 8 SWG bare copper conductor running from earth plate to MPB and to all FDBs including the necessary connecting, fixing and jointing materials as well as excavation and backfilling works as per drawing. Specification, electricity rules and instruction all complete.for Generator & panel board.	Set	3			
3	Supply delivery Installation of 300A 4 pole Change over front handel incloser type switch 415 volt	Set	1			
4	Supply delivery Installation of 400A TP MCCB 50 KA adjustable for panel board.	Set	1			
5	95sq.mm Cable shoe	Nos	30			
6	50sq.mm Cable shoe	Nos	20			
7	25sq.mm Cable Shoe	Nos	30			
8	Earthing wire 10 Swg	Meter	40			
9	HDP pipe 16mm	Kg	5			
10	PVC Tape (RYBN)	Nos	20			
	Total					
	Vat 13%					
	Total Amount with Vat					

Name of firm:

Signature:

Seal of Firm: